ANNEXURE - II

Construction of Boundary Wall in Campus of Doctor's Quarter										
S.No.	Item No.	Description of Items	No.	Length (ft.)	Breadth (ft.)	Height (ft.)	Quantity	Unit	Rate (M2)	Amount (Rs.)
1	5.1.1+ 5.1.2	E/W in excavation in foundation trenches in Hard soil		35.00	2.00	2.50	175.00	cft		
							4.95	M3		
2	5.1.10	Providing Sand Filling in foundation --- do ---- complete job		35.00	2.00	0.50	35.00	cft		
							0.99	M3		
3	5.6.3	Providing 75B Bricks flat soling		35.00	2.00		70.00	sft.		
							6.50	M2		
4	5.3.1.2	Providing P.C.C. (1:2:4) in foundation ----do---- complete job		35.00	2.00	0.50	35.00	cft.		
							0.99	M3		
5	5.2.6	Providing 75B Bricks work in C.M. (1:6) in foundation & plinth ----do---- complete job		35.00	1.25	1.25	56.69	cft.		
				35.00	0.83	6.00	174.30	cft		
		Caping		35.00	1.25	0.25	10.94	cft.		
		Total					241.93	cft.		
							6.85	M3		
6	5.7.3	Providing C.P. (1:6) on walls ----do---- complete job								
		Wall	2	35.00	6.25		437.50	sft		
		Top		35.00	1.25		43.75	sft.		
		Total					481.25	sft.		
							44.72	M2		
7	13.48. 1	Providing with Deluxe multi surface paint for exteriors ---do---complete job								
		Area wide Item No. - 5					44.72	M2		
8		Carriage of Materials								
		a) Sand - Lead - 10 Km					5.43	M3		
		b) Stone Chips - Lead - 22 km					0.89	M3		
		c) Bricks (1K+7P)					4893	Nos.		
		Total								